


[View All Notifications](#)

Form View

[Go Back to Tender/Proposal Document](#)

Tender/Proposal Detail

Tender/Proposal ID : 541339 **Invitation Reference No. :** T-1/1757 Dated: 25/01/2021

Closing Date and Time : 25-Feb-2021 13:00 **Opening Date and Time :** 25-Feb-2021 13:00

Procuring Entity : Chattogram O&M Division-1, BWDB

Brief : Slope Protection Work of Sea-Dyke from KM 34.420 to KM 34.720 = 300m. in connection with "Rehabilitation of Coastal Polder No. 62 (Patenga), Polder No. 63/1A (Anowara), Polder No. 63/1B (Anowara & Patiya) in Chittagong District" during the FY 2020-2021 & 2021-2022

[View Notice](#)

Form Name : Bill of Quantities

Table Name : Bill of Quantities

Item no.	Group	Item Code (if any)	Description of Item	Measurement Unit	Quantity	Unit Price In figures (BDT)	Unit Price In Words (BDT)	Total Price In Figures (BDT)	Total Price In Words (BDT)
1	04-180	04-180	Site preparation by manually removing all miscellaneous objectional materials from entire site and removing soil upto 15cm depth including uprooting stumps, jungle clearing, levelling dressing etc. complete as per direction of Engineer in charge.	Sqm	12000.000	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
2	16-220	16-220-30	Earth work by carried earth (by truck/boat or any other means) supplied at contractor's own cost (including royalty) in constructing/ resectioning of the embankment/ canal bank/ road etc. compacted to 85%/90% maximum dry density at optimum moisture content with reference to laboratory density test AASHTO modified hammer, with clayey soil (minimum 30% clay, 0-40% silt and 0-30% sand) beyond initial lead of 300m including throwing the spoils to profiles in layer not exceeding 230mm in thickness with clod breaking to maximum size of 100mm, benching the side slopes, removing roots and stumps of trees of girth upto 200mm, stripping/ ploughing the base of embankment and borrow pit area, dug bailing, clearing jungles, bail out of water, rough dressing including 150mm cambering at the centre of crest with all leads and lifts complete (compaction will be done by the contractor with approved equipment including all ancillary charges for compaction and testing) as per direction of Engineer in charge. 300m to 1.00 km. 90% compaction .	Cum	56181.430	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
3	40-550	40-550-30	Supplying & laying sand as filter layers as per specific size range & gradation in/c. preparation of surface, compacting in layer etc. comp. with supply of all materials & as per direction of ENGINEER IN CHARGE. FM 1.00 to 1.50	Cum	2414.013	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
4	40-520	40-520-20	Supplying & laying dry 1st. class or pick jhama chips as filter in two layers(top and bottom) as per specific size, range and gradation, in/c. breaking chips, grading, preparation of surface, compacting each layer etc. comp. with supply of all materials & as per direction of ENGINEER IN CHARGE. Well graded between 40mm to 20mm size.	Cum	1417.341	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
5	40-520	40-520-30	Supplying & laying dry 1st. class or pick jhama chips as filter in two layers(top and bottom) as per specific size, range and gradation, in/c. breaking chips, grading, preparation of surface, compacting each layer etc. comp. with supply of all materials & as per direction of ENGINEER IN CHARGE. Well graded between 20mm to 5mm size.	Cum	1417.341	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
6	40-590	40-590	Supplying and dumping/laying in position 2nd class brick bats of specified sizes (not less than 1/3rd brick) on bed, slopes or any other places by any means as per direction of Engineer in charge.	Cum	1770.542	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
7	40-500	40-500-40	"Supplying and placing non-woven needle punched type geotextile fabric (100% Polypropylene Fabric, unit weight : 855 Kg/m3 to 946 Kg/m3) as filter materials of elongation at maximum force machine direction (MD) >=60% and <= 100 % , elongation at maximum force (CMD) => 40% and <= 100% , horizontal and vertical permeability (under 2 kn/m ² pressure)=>2x10E-3 m/sec. for effective erosion protection in hydraulic structures/river training works including local handling, placing in position, providing machine seamed joints (with 100% polypropylene or nylon thread) or 35cm lap in dry condition or minimum 100cm lap under water including protecting the geotextile material from UV ray and from any other damages including supply of all materials, labours, equipment? s etc. complete as per direction of Engineer in charge. (Geotextile delivered at site should be certified by ISO and clearly labelled with brand name and grade printed at regular intervals across the body of the fabric)." Mass =>400 gm/m ² , thickness(Under 2 kpa pressure) =>3.00 mm, EoS<=0.08mm, strip tensile strength =>23 kn/m, grab strength =>1500 N, CBR puncture resistance =>3800 N.	Sqm	26297.631	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
8	40-	40-	Manufacturing and supplying C.C. blocks in leanest mix. 1:2:4 with	Nos.	16471.000	Fill By	Auto	Auto	Auto

	230-01	230-01	cement, sand (FM>=2.0) and Stone Chips (40mm down graded) to attain a 28 days cylinder strength of 18 N/mm ² including grading, washing stone chips, mixing, laying in forms, consolidation, curing for at least 21 days, including preparation of platform, shuttering and stacking in measurable stacks etc. complete including supply of all materials (steel shutter to be used) as per direction of Engineer in charge. Block size : 1000 x 800 x 600			Tenderer/Consultant - Money Positive(3 digits after decimal)			
9	40-170	40-170-80	Manufacturing and supplying C.C. blocks in leanest mix. 1:3:5.5 with cement, sand (FM>=1.5) and Stone Chips (40mm down graded) to attain a 28 days cylinder strength of 10.5 N/mm ² including grading, washing stone chips, mixing, laying in forms, consolidation, curing for at least 21 days, including preparation of platform, shuttering and stacking in measurable stacks etc. complete including supply of all materials (steel shutter to be used) as per direction of Engineer in charge. Block size : 500 x 500 x 600	Nos.	2205.000	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
10	40-170	40-170-20	Manufacturing and supplying C.C. blocks in leanest mix. 1:3:5.5 with cement, sand (FM>=1.5) and Stone Chips (40mm down graded) to attain a 28 days cylinder strength of 10.5 N/mm ² including grading, washing stone chips, mixing, laying in forms, consolidation, curing for at least 21 days, including preparation of platform, shuttering and stacking in measurable stacks etc. complete including supply of all materials (steel shutter to be used) as per direction of Engineer in charge. Block size : 500 x 500 x 400	Nos.	6955.000	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
11	40-170	40-170-90	Manufacturing and supplying C.C. blocks in leanest mix. 1:3:5.5 with cement, sand (FM>=1.5) and Stone Chips (40mm down graded) to attain a 28 days cylinder strength of 10.5 N/mm ² including grading, washing stone chips, mixing, laying in forms, consolidation, curing for at least 21 days, including preparation of platform, shuttering and stacking in measurable stacks etc. complete including supply of all materials (steel shutter to be used) as per direction of Engineer in charge. Block size : 500 x 500 x 200	Nos.	23162.000	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
12	40-270	40-270-20	Labour charge for protective works in laying CC blocks of different sizes including preparation of base, watering and ramming of base etc. complete as per direction of Engineer in charge. 200m. to 500m	Cum	14087.120	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
13	40-560	40-560	Labour charge for salvaging of cement concrete/sand cement/brick blocks of different sizes including carriage within the site of any protective work with all leads and lifts and stacking in measurable stacks as per direction of Engineer in charge.	Cum	3996.750	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
14	28-120	28-120-50	Cement concrete work in leanest mix. 1:3:6 with sand of FM>=1.5, in foundation or floor including breaking, screening, grading and washing aggregates with clear water, mixing, laying in position, consolidation to levels, curing, including supply of all materials, excluding the cost of formworks etc. complete as per direction of Engineer in charge. With 40mm downgraded stone chips.	Cum	11.00	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
15	40-480	40-480-20	Supplying , filling and placing of Geo-Tube, making with standard geotextile (100% Polypropylene fabric, unit weight : 855 Kg/m ³ to 946 Kg/m ³ , geo-textile thickness ≥ 4.00 mm, mass ≥ 550 gm/m ² , EOS≤0.075 mm) and sewing in accordance with the detailed drawing and Technical Specifications included in the Tender Document and Schedule of Rates of BWDB, filling hydraulically with Sand (minimum 80% sand must be retained on sieve no 100), sewing along one transverse (top) side after filling, including carrying, placing in position in the site as per approved design, cost of all materials & equipments and its mobilization, labour, incidental charges etc. complete as per direction of Engineer in Charge. Geo Tube: Diameter= 1.25 m	m.	1800.000	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
16	04-710	04-710	Temporary lease of land for 1 (one) year with necessary compensation for crops or this installation on land for site office, material yard, casting yard, staking yard etc. complete as per direction of Engineer in charge.	Sqm	8046.790	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
17	04-700	04-700-10	"Erection and maintenance of site office and removal of the same after completion of work as per approved plans & drawings for the use of the Engineer-in-charge & his staff, Task force and field laboratory with adequate foundation, brick walls, acceptable outside & inside wall surface, concrete floor with floor tiles, false ceiling of gypsum board, windows are to be glazed & provided with steel grill & screen/blinds, doors with approved locks, furniture & fittings of approved quality, equipment & plant of approved quality, electricity, running water, sewerage, security fencing, 5 KVA stand-by generator, IBM compatible PC with monitor, uninterruptible power supply (UPS), LaserJet printer (minimum 25 ppm), first aid-box, safety helmet, level/theodolite/EDM, consumables, stationeries, day & night guards & a tea boy and site office shall be ready for occupation by the Engineer-in-charge within 28 days of commencement of work, etc. complete as per direction of Engineer-in-charge. (This is a time related item; proportionate payment for this item shall be made distributing in each bill on the basis of percentage progress of the whole works under contract) " Site office of minimum 38 sqm plinth area.	Nos.	1.00	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
18	48-100	48-100	Fine dressing and close turfing of the slopes and the crest of embankment with 75mm thick, good quality durba or charkanta sods of size 200mm x 200mm, with all leads and lifts, including ramming, watering until the turf grows properly, maintaining etc. complete (measurement will be given on well grown grass only). as per direction of Engineer in charge.	Sqm	4635.480	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
19	40-920	40-920	Earth work in cutting and filling of eroded bank of river, channel etc. to design slope, including levelling, dressing and compacting the earth in 150mm layers and preparation of the base for bank protection work and use the excess material for filling the ditches on the bank within 50 m or specified in the drawing, if no ditches to be filled then excess material shall be disposed of at least 100 m from the bank line on C/S etc. complete as per direction of Engineer in charge.	Cum	7685.040	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto

20	56-100	56-100	Earth work in box cutting up to 1.00 m depth, in all kinds of soil with all leads, removing the spoils to a safe distance, including levelling and dressing, maintaining required cambering etc. complete, as per direction of Engineer in charge.	Cum	8400.000	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
21	56-110	56-110	Construction of improved road sub-grade of sand (FM>=0.8) in maximum 150mm thick layer including dressing, levelling, ramming, watering, cambering and compacting to attain minimum CBR-8% by manual labour using mallet/ vibro compactor and compacted to 95% of maximum dry density including cost of all materials etc. complete as per design, drawing and direction of Engineer in charge (payment shall be made on compacted volume).	Cum	3600.000	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
22	56-120	56-120-10	Brick flat soling with 1st class bricks, including preparation of bed, sand blinding (FM>=0.5), levelling, dressing including supply of all materials etc. complete as per direction of Engineer in charge. Single layer.	Sqm	24000.000	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
23	56-130	56-130	Brick on edge soling in Herring Bone Bond (HBB) with 1st class bricks, including preparation of bed, sand blinding (FM>=0.5), levelling, dressing including supply of all materials etc. complete as per direction of Engineer in charge.	Sqm	24000.000	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
24	56-140	56-140-10	Brick on end edging (single layer) across the road, with 1st class bricks, including cutting trenches true to level and grade, sand filling (FM>=0.5), 40mm thick, sand blinding, levelling, dressing, ramming sides properly including supply of all materials etc. complete as per direction of Engineer in charge. 75 mm thick.	m.	16000.000	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
25	16-720	16-720-10	Filling ditch/pond/channel/khal etc or land development/improvement by dredged earth from river bed (all kind of soil but excluding organic material) , carried by Bulkhead/cargo/boat or any other mean, loading and unloading/Disposing/placing the dredged materials in the designated area upto 1 km from river bank by bulkhead dredger including , maintaining slopes, levelling and dressing in layers upto finished level with all lifts & leads etc. all complete as per direction of the Engineer in charge. Bulkhead/cargo/boat or any other means: within 1 km along the river.	Cum/Km	73496.750	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
26	16-720	16-720-10	Filling ditch/pond/channel/khal etc or land development/improvement by dredged earth from river bed (all kind of soil but excluding organic material) , carried by Bulkhead/cargo/boat or any other mean, loading and unloading/Disposing/placing the dredged materials in the designated area upto 1 km from river bank by bulkhead dredger including , maintaining slopes, levelling and dressing in layers upto finished level with all lifts & leads etc. all complete as per direction of the Engineer in charge. "Bulkhead/cargo/boat or any other means: 2nd km and above."	Cum/Km	73496.750	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
						Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto