


[View All Notifications](#)

Form View

[Go Back to Tender/Proposal Document](#)

Tender/Proposal Detail

Tender/Proposal ID : 552225 **Invitation Reference No. :** Da-1/1184 Date : 07-03--2021
Closing Date and Time : 05-Apr-2021 11:08 **Opening Date and Time :** 05-Apr-2021 11:08
Procuring Entity : Moulvibazar O&M Division
Brief : ML-PW-41
 Bank Revetment work along the left bank at volanagar-mithipur from km 37.135 to 38.085950m with 1 nos. R/S stair in C/W Protection Project at Moulvibazar Sadar Rajnagar & Kulaura Upazilla from erosion of Manu river under Moulvibazar O & M Division BWDB Moulvibazar during the FY 2020-21 & 2021-22.

[View Notice](#)
Form Name : Bill of Quantities

Table Name : Bill of Quantities

Item no.	Group	Item Code (if any)	Description of Item	Measurement Unit	Quantity	Unit Price In figures (BDT)	Unit Price In Words (BDT)	Total Price In Figures (BDT)	Total Price In Words (BDT)
1	04-120	04-120	"Construction of B.M. Pillars at site with first class bricks in cement mortar (1:4) of size 38cmx38cmx75cm on cement concrete (1:2:4) base of size 50cmx50cmx7.5cm with 12mm thick cement plastering (1:2) on exposed surfaces of pillar and cement mortar on top (1:2), with inscription of BWDB"" with 25cm of the pillar below ground level etc. complete including ramming the backfill and the cost of all materials as per direction of Engineer in charge.	Nos	2.00	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
2	04-180	04-180	Site preparation by manually removing all miscellaneous objectional materials from entire site and removing soil upto 15cm depth including uprooting stumps, jungle clearing, levelling dressing etc. complete as per direction of Engineer in charge.	Sqm	19000.00	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
3	16-100	16-100	"Erection of bamboo profile with full bamboo posts and pegs not less than 60mm in diameter and coir strings etc. complete as per direction of Engineer in charge.	Nos	20.00	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
4	MR	MR	Manufacturing, Supplying, Installation and fitting fixing a signboard 1.00 m x 1.50 m size including supply of all necessary materials etc. complete as per direction of Engineer in charge.	Nos	2.00	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
5	40-920	40-920	Earth work in cutting and filling of eroded bank of river, channel etc. to design slope, including levelling, dressing and compacting the earth in 150mm layers and preparation of the base for bank protection work and use the excess material for filling the ditches on the bank within 50 m or specified in the drawing, if no ditches to be filled then excess material shall be disposed of at least 100 m from the bank line on C/S etc. complete as per direction of Engineer in charge.	Cum	27977.00	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
6	40-370	40-370-20	""[Dumping with Boat & Total Station] Supplying, filling and dumping of geo-textile bags of different sizes and capacity at project/work site, making with standard geo-textile fabric (97% Polypropylene fabric with 3% additives, mass>= 400gm/m ² , unit weight : 855 Kg/m ³ to 946 Kg/m ³ , EOS<=0.075 mm) Test of service life according to ISO 13438:2018. Test of exposure time according to EN 12224: 2000) and sewing in accordance with the drawing and Technical Specifications of BWDB and Schedule of Rates of BWDB, protecting the geotextile bags from UV ray or any other damages, filling with sand (dry and minimum 80% sand must be retained on sieve no 100), sewing along one transverse (top) side after filling, staking in measurable/ countable stakes, marking by synthetic enamel paint during counting, dumping from properly positioned and anchored flat top engine boat over an area as per drawing, maintaining & recording the position of dumping boat using total station including loading, unloading, sequential piling of geo-bags on the dumping edge of boat, carrying geo-bags from stake-yard to dumping place by head load and power driven flat top country boat, cost of all materials & equipments and its mobilization, labour, incidental charges etc complete as per technical specification, approved design and direction of Engineer in charge.[fill volume and weight will be measured after filling with dry sand]""	Nos	20404.00	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
			"						

			40-370-20 Geo-bag; inner size:1075mmx850mm, outer size:1125mmx900 mm , geo-fabric th.=>3.0mm, Fill Vol: 0.1164cum; wt: 175kg						
7	40-680	40-680-30	"Supplying, sizing and placing in position local hard wood bullah such as Sonali gul, Tetul, Jam etc. including all taxes and incidental charges (bullah measured at 1/3rd. length from thick end excluding the bark) etc. complete as per direction of Engineer in charge. " 40-680-30 Above 15 cm to 18 cm. dia	m	7608.00	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
8	40-690	40-690-30	"Labour charge for driving local hard bullah such as Sonali gul, Tetul, Jam etc. bullah piles on dry land, by monkey hammer etc. complete including charges for all equipments as per direction of Engineer in charge. " 40-690-30 Above 15 cm to 18 cm. dia	m	7354.40	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
9	40-190	40-190-35	"Manufacturing and supplying C.C. blocks in leanest mix. 1:2.5:5 with cement, sand (FM>=1.5) and Stone Chips (40mm down graded) to attain a 28 days cylinder strength of 12 N/mm ² including grading, washing stone chips, mixing, laying in forms, consolidation, curing for at least 21 days, including preparation of platform, shuttering (steel shutter to be used) and stacking in measurable stacks, cost of all materials and charges, etc. complete as per direction of Engineer in charge. " 40-190-35 Block Size: 40cmx40cmx40cm	Nos	47000	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
10	40-190	40-190-50	"Manufacturing and supplying C.C. blocks in leanest mix. 1:2.5:5 with cement, sand (FM>=1.5) and Stone Chips (40mm down graded) to attain a 28 days cylinder strength of 12 N/mm ² including grading, washing stone chips, mixing, laying in forms, consolidation, curing for at least 21 days, including preparation of platform, shuttering (steel shutter to be used) and stacking in measurable stacks, cost of all materials and charges, etc. complete as per direction of Engineer in charge. " 40-190-50 Block Size: 30cmx30cmx30cm	Nos	70370	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
11	40-190	40-190-40	"Manufacturing and supplying C.C. blocks in leanest mix. 1:2.5:5 with cement, sand (FM>=1.5) and Stone Chips (40mm down graded) to attain a 28 days cylinder strength of 12 N/mm ² including grading, washing stone chips, mixing, laying in forms, consolidation, curing for at least 21 days, including preparation of platform, shuttering (steel shutter to be used) and stacking in measurable stacks, cost of all materials and charges, etc. complete as per direction of Engineer in charge. "	Nos	118260	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto

			40-190-40 Block Size: 40cmx40cmx20cm						
12	40-290	40-290-10	Dumping work of Hard rock/ stone/ boulders/C.C blocks/brick blocks/sand cement blocks over a uniform area from properly positioned by engine boat upto an accuracy of 10cm monitoring with Total Station. The dumping area to be determined by conducting bathymetric survey, furnishing topographic site plan, cross section, dumping alignment, providing location of benchmark and stake at batches of dumping activity, doing by a river survey team (including survey manager, hydrographic surveyor, Auto cad operator, etc.) with total station. Sequential stacking of Hard rock/ stone/ boulders/C.C blocks/brick blocks/ sand cement blocks on the engine boat, carrying the Hard rock/stone/ boulders/C.C blocks/brick blocks/sand cement blocks to dumping area and dumping the block from the boat by manual labour or any other means, all materials & charges etc. complete as per direction of engineer in charge, specification and design. 40-290-10 Within 200 m.	Cum	3926.39	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
13	40-290	40-290-20	Dumping work of Hard rock/ stone/ boulders/C.C blocks/brick blocks/sand cement blocks over a uniform area from properly positioned by engine boat upto an accuracy of 10cm monitoring with Total Station. The dumping area to be determined by conducting bathymetric survey, furnishing topographic site plan, cross section, dumping alignment, providing location of benchmark and stake at batches of dumping activity, doing by a river survey team (including survey manager, hydrographic surveyor, Auto cad operator, etc.) with total station. Sequential stacking of Hard rock/ stone/ boulders/C.C blocks/brick blocks/ sand cement blocks on the engine boat, carrying the Hard rock/stone/ boulders/C.C blocks/brick blocks/sand cement blocks to dumping area and dumping the block from the boat by manual labour or any other means, all materials & charges etc. complete as per direction of engineer in charge, specification and design. 40-290-20 200 m to 500m	Cum	981.60	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
14	40-550	40-550-30	Supplying and laying sand as filter layers as per specific size ranges and gradation including preparation of surface, compacting in layer etc. complete with supply of all materials and as per direction of Engineer in charge. 40-550-30 FM : 1.0 to 1.5	Cum	2221.63	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
15	40-500	40-500-40	"Supplying and placing non-woven needle punched type geotextile fabric (97% Polypropylene Fabric with 3% additives, mass>= 400gm/m², unit weight : 855 Kg/m³ to 946 Kg/m³, EOS<= 0.075 mm, Test of service life according to ISO 13438:2018. Test of exposure time according to EN 12224: 2000) as filter materials of elongation at maximum force machine direction (MD) >=60% and <= 100 % , elongation at maximum force (CMD) => 40% and <= 100% ,horizontal and vertical permeability (under 2 kn/m² pressure)=>2x10E-3 m/sec. for effective erosion protection in hydraulic structures/river training works including local handling, placing in position, providing machine seamed joints (with 100% polypropylene or nylon thread) or 35cm lap in dry condition or minimum 100cm lap under water including protecting the geotextile material from UV ray and from any other damages including supply of all materials, labours, equipment's etc. complete as per direction of Engineer in charge. "	Sqm	24187.50	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto

			40-500-40 Mass =>400 gm/m ² , thickness(Under 2 kpa pressure) =>3.00 mm, EoS<=0.08mm, strip tensile strength =>23 kn/m, grab strength =>1500 N, CBR puncture resistance =>3800 N.						
16	40-520	40-520-20	Supplying and laying dry 1st class or pick jhama chips as filter in two layers (top and bottom) as per specific size, range and gradation, including breaking chips, grading, preparation of surface, compacting each layer etc. complete with supply of all materials and as per direction of Engineer in charge. 40-520-20 Well graded between 40mm to 20mm size.	Cum	1110.81	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
17	40-520	40-520-30	Supplying and laying dry 1st class or pick jhama chips as filter in two layers (top and bottom) as per specific size, range and gradation, including breaking chips, grading, preparation of surface, compacting each layer etc. complete with supply of all materials and as per direction of Engineer in charge. 40-520-30 Well graded between 20mm to 5mm size. (Combination of sub-item 10 & 30 or 20 & 30 shall be used)	Cum	1110.81	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
18	40-270	40-270-10	Labour charge for protective works in laying CC blocks of different sizes including preparation of base, watering and ramming of base etc. complete as per direction of Engineer in charge. 40-270-10 Within 200 m.	cum	3103.14	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
19	40-270	40-270-20	Labour charge for protective works in laying CC blocks of different sizes including preparation of base, watering and ramming of base etc. complete as per direction of Engineer in charge. 40-270-20 200 m to 500m	cum	775.79	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
20	28-120	28-120-20	Cement concrete work in leanest mix. 1:3:6 with sand of FM>=1.5, in foundation or floor including breaking, screening, grading and washing aggregates with clear water, mixing, laying in position, consolidation to levels, curing, including supply of all materials, excluding the cost of formworks etc. complete as per direction of Engineer in charge. 28-120-20 With 25mm down graded stone chips.	Cum	23.50	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
21	76-120	76-120-10	M.S. Work for reinforcement with deformed M.S. bar, fy=400 N/mm ² , (made from billet) in RCC works, including local handling, cutting, forging, bending, cleaning and fabrication with supply of deformed M.S. bar in different sizes and binding with 22 to 18 gages G.I. wire etc. complete including the cost of all materials as per direction of Engineer in charge. 76-120-10 8mm dia to 30mm dia.	Kg	1557.33	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
22	28-200	28-200-10	Reinforced cement concrete work in leanest mix. 1:1.5:3, with 20mm down graded coarse aggregates and sand of FM>2.0 to FM<=2.5, to attain a minimum 28 day cylinder strength of 22.0 N/mm ² , including breaking, screening, grading, washing aggregates with clean water, mixing, laying in forms, consolidation to levels, curing, including supply of all materials, excluding cost of M.S. work for reinforcements and formworks etc. complete and as per direction of Engineer in charge. 28-200-10 With stone chips.	Cum	24.11	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
23	16-500	16-500	Earth work in excavation of foundation trenches in all kinds of soils including levelling, dressing, placing, removal of spoils to a safe distance with initial lead of 30m and lift of 1.5m as per direction of Engineer in charge.	Cum	13.65	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto

24	36-330	36-330	Form work for centering and water tight shuttering as per drawing with 28 BWG plain GI sheet cover over minimum 25mm thick wooden plank with batten (75mmx50mm), struts, 60-80mm dia bamboo props etc. as required in stair case, arch or other similar ornamental works including fitting, fixing by nails, tie rods, nuts & bolts to desired shape and size including levelling and removing the formworks etc. after specified period including the cost of all materials as per direction of Engineer in charge.	sqm	113.32	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
25	24-100	24-100-10	Minimum 20mm thick sand cement plaster, (sand of FM>=1.3) in ground floor, including scaffolding, raking out joints, making sharp edges and corners, cleaning the surface, curing for at least seven days etc. complete including the cost of all materials and as per direction of Engineer in charge. 24-100-10 proportion 1:4	Sqm	22.63	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
26	72-260	72-260-10	Weather Coat of approved quality and colour (delivered from authorized local agent of the Manufacturer in a sealed container) on exterior surface applying as per manufacturer instructions including cleaning the surface with wire brush, provision of necessary scaffolding, cleaning doors & windows, ventilators by washing including cost of water, electricity & other charges etc. complete in all respect as per direction of Engineer in charge. 72-260-10 Applying of Weather coats to exterior surface: 2 coats	Sqm	22.63	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
27	16-220	16-220-30	Earth work by carried earth (by truck/boat or any other means) supplied at contractor's own cost (including royalty) in constructing/ resectioning of the embankment/ canal bank/ road etc. compacted to 85%/90% maximum dry density at optimum moisture content with reference to laboratory density test AASHTO modified hammer, with clayey soil (minimum 30% clay, 0-40% silt and 0-30% sand) beyond initial lead of 300m including throwing the spoils to profiles in layer not exceeding 230mm in thickness with clod breaking to maximum size of 100mm, benching the side slopes, removing roots and stumps of trees of girth upto 200mm, stripping/ ploughing the base of embankment and borrow pit area, dug bailing, clearing jungles, bail out of water, rough dressing including 150mm cambering at the centre of crest with all leads and lifts complete (compaction will be done by the contractor with approved equipment including all ancillary charges for compaction and testing) as per direction of Engineer in charge. 16-220-30 300m to 1.00 km. 90% compaction;	cum	36614.40	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
28	48-100	48-100	Fine dressing and close turfing of the slopes and the crest of embankment with 75mm thick, good quality durba or charkanta sods of size 200mm x 200mm, with all leads and lifts, including ramming, watering until the turf grows properly, maintaining etc. complete (measurement will be given on well grown grass only) as per direction of Engineer in charge.	Sqm	15976.50	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
29	04-710	04-710	Temporary lease of land for 1 (one) year with necessary compensation for crops or this installation on land for site office, material yard, casting yard, staking yard etc. complete as per direction of Engineer in charge.	Sqm	23750.00	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto
30	04-700	04-700-10	Erection and maintenance of site office and removal of the same after completion of work as per approved plans & drawings for the use of the Engineer-in-charge & his staff, Task force and field laboratory with adequate foundation, brick walls, acceptable outside & inside wall surface, concrete floor with floor tiles, false ceiling of gypsum board, windows are to be glazed & provided with steel grill & screen/blinds, doors with approved locks, furniture & fittings of approved quality, equipment & plant of approved quality, electricity, running water, sewerage, security fencing, 5 KVA stand-bye generator, IBM compatible PC with monitor, uninterruptible power supply (UPS), LaserJet printer (minimum 25 ppm), first aid-box, safety helmet, level / the odolite/EDM, consumables, stationeries, day & night guards & a tea boy and site office shall be ready for occupation by the Engineer-in-charge within 28 days of commencement of work, etc. complete as per direction of Engineer-in-charge. (This is a time related item; proportionate payment for this item shall be made distributing in each bill on the basis of percentage progress of the whole works under contract)	Each	1.00	Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto

			04-700-10 Site office of minimum 38 sqm plinth area.						
						Fill By Tenderer/Consultant - Money Positive(3 digits after decimal)	Auto	Auto	Auto

